



## 10011976 - FTTP MDU Level 3 Wall Box XL

## **Product Overview**

A larger sized cabinet is intended for fiber splicing and termination of up to 192 microducts (subscribers). This is suitable when changing from distributed Air Blown Fiber to fiber optical cables, or to other ducts for further fiber blowing.

The supplied fiber organizers can easily handle 384 fibers (typically). The cabinet is also excellent for jointing cables indoors.

## **Features**

- IP45 Indoor, Wall & Rack mountable
- 384 fibers / 192 microducts
- 28 assemblies or 8 cable inlets
- Lockable and foldable door, forming an installation work table
- Front serviced

## Design

The cabinet is designed for indoor use according to IP 45 but can be fitted conveniently in outdoor enclosures. It is designed for wall mounting, but also fits in 19" or ETSI racks. Cable and duct entrances are supplied. The cabinet is painted in coral white color, delivered with microduct and fiber organizers, fiber labels & 2 keys to the lockable doors

Ordering Information	
Part number	Description
FCLW-L-L3-SPL-16X04-UNL	FTTP MDU Level 3 Wall Box - Large - Splice/Split - Fitted With 16x 1x4 Splitters - Includes Wall Mounting [For Indoor Use]

